

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: DILL T 28 S, R 6 W , Sec 32

Set By (Agency): DCSO

Date Set: 1973

Recovered By RS, SF


Date Recovered 2/27/84

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



d-045
DILL

28S 6W 32

NAD 535290.32 4139142.99
83 43° 5'53" 123°25'45"

VERTICAL CONTROL NGVD 29 CORPSCON 6 NAVD 88 536.94 FT

Elevation: 533.49 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCPW Proj. # _____ Date: 1974

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 535,325.45 X(Easting) 1,218,184.74

Precision: 1/10,000 Agency: DCSO Proj. # 2004 CS56/23 Date: 1973 - 1984

Approximate Geographic Position: Latitude 43°05'53" Longitude 123°25'40"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "DILL 1973" set in concrete sidewalk at the N.E. end of bridge over the South Umpqua River.

TO REACH:

From the intersection of State Hwy.99 and Co. Rd. #47 (Brockway, Lookingglass Rd.) in T28S, R6W, Sec.32, proceed westerly along Co. Rd. #47 approx. 300 ft. to bridge over South Umpqua River and monument in N.E. corner of bridge.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.