

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: F-253 T 27 S, R 5 W, Sec 24

Set By (Agency): Or. Geod. Sur.

Date Set: 1934

Recovered By RWS,SJF


Date Recovered 1/87; F20K 1/03

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



f-002  
F 253

NAD 573267.85 4190501.25  
83 43°12'25" 123°14'30"

VERTICAL CONTROL NGVD 29 (CORPCON 6 NAVD08 587,281)

Elevation: 583.788 NGS Line # 94 USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 1st Agency: USC&GS Proj. # \_\_\_\_\_ Date: 1961

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 573,303.28 X(Easting) 1,269,542.80

Precision: 1/25,000 Agency: DCSO Proj. # 2004-19 Date: 1980


Approximate Geographic Position: Latitude 43°12'25" Longitude 123°14'25"

DESCRIPTION and TO REACH

SKETCH

A Oregon Geodetic Survey disk stamped  
"583 F253 1934" set in a concrete post.

Go to the intersection of Co. Rd. #16  
(Dixonville, Roberts Creek, Carnes Rd.)  
and Co. Rd. #17 (Little River, Buckhorn Rd.)  
in T27S,R5W,Sec.24, monument is in southeast  
corner of intersection.



Reference Marks:

A DCSO disk stamped "DIXIE 1980)  
bears N 82° 24' 13" W, 111.73 ft. (grid).

A DCSO disk stamped "DIXIE RM1 1980"  
bears N 52°55'00" W, 130.50 ft. (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.