

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR


Station: GREG  
 Set By (Agency): DCSO  
 Date Set: 1974  
 Recovered By FLI (DCSO)  
 Date Recovered 6-15-84  
 Recovered By O.D.O.T.  
 Date Recovered 9-10-98  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_

T 27 S, R 6 E, Sec 8 <sup>UNS</sup>



g-043  
GREG 27S 6E 8

NAD 576566.75 4483219.92  
 83 43°14'13" 122° 8'38"



VERTICAL CONTROL NGVD 29 CORPSCON 6 NAVD88 4825.442 FEET

Elevation: 4821.186 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: 2nd Agency: DCSO Proj. # 2004-8 Date: 1974

HORIZONTAL CONTROL OCS 27


South Zone State Plane Coordinates: Y(Northing) 576,604.34 X(Easting) 1,562,258.12  
 Precision: 1/25,000 Agency: DCSO Proj. # 2004-8 CS57/23 Date: 1975  
 Approximate Geographic Position: Latitude 43°14'13" Longitude 122°08'34"

DESCRIPTION and TO REACH

At junction of Hwy 138  
 and USFS Road No. 4793  
 (formerly 2711) on cut-bank  
 N.E. of intersection.

B.C. set in 6" bell tile.  
 20 ft. from Road No. 4793  
 and 30 ft. from Hwy 138.

SKETCH



Reference Marks: (Greg R.M. 2 R.M. 2 DESTROYED (ODOT 98)  
 B.C. in 6" bell tile (El. 4813.815)  
 576,587.46 1,562,153.68

BM S-480 B.C. in concrete post (El. 4814.400)  
 576,499.87 1,562,203.84

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.