

2/82


OFFICE OF THE

g-056
GWM 64

26S 7W 24

DOUGLAS COUNTY SURVEYOR

NAD 608012.96 4129148.92
83 43°17'47" 123°28'34"



T 26 S, R 7W, Sec. 24

Station: GWM 64

Set By (Agency): USGS

Date: 1942

NGVD 29

VERTICAL CONTROL **CORRSCON 6 NAVD 88 447.354 FT**

Elevation: 443.864 NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision 2nd Agency: DCSO Proj. #: 2007 Date: 1991

HORIZONTAL CONTROL

OCS 27

Oregon State Plane Coordinates: Y(Northing) 608,047.86 X(Easting) 1,208,190.29
(South Zone)

Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1974
(River Flood Plain)


Approximate Geographic Position: Latitude= 43°17'47" Longitude= 123° 28' 30"

DESCRIPTION: Monument is a brass cap
set in conc. steps.

To reach: From Melrose store proceed
N'thly along Co. Rd. #59 to inter-
section with Co. Rd. #13. Turn right
and proceed along #13 to intersection
with Co. Rd. #143. Monument is
located on bottom step of church
building. It is level with road
surface and approx. 15' right of
centerline. See sketch.

VICINITY: Umpqua-Melrose Rd. North of
Melrose near Cleveland Cemetary.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.