

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: H 500 T 30 S, R 2W , Sec 33

Set By (Agency): USC&GS

Date Set: 1949

Recovered By JP-RS


Date Recovered 3-18-82

Recovered By RWS,SJF

Date Recovered 8/14/85

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



n-007  
H 500

30S 2W 33

NAD 469478.40 4263721.64  
83 42°55'42" 122°57'20"

VERTICAL CONTROL NGVD 29 CORPSCON 6 NAVD88 1032.077 FT.

Elevation: 1028.587 NGS Line # 130 USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2010-2 Date: 1957

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 469,514.73 X(Easting) 1,342,763.06

Precision: 1/25,000 Agency: DCSO Proj. # 2010-2 Date: 1975


Approximate Geographic Position: Latitude 42°55'43" Longitude 122°57'16"

DESCRIPTION and TO REACH

Found: A standard USC&GS disk stamped "H 500 1949" set flush on 2 ft. square block of concrete. Witness post and sign bear West 1.0 ft..

To Reach: From the intersection of Hwy. 227 and Co. Rd. 46 (Tiller-South Umpqua) in S. 33 T30S, R2W, proceed Westerly along Hwy. 227 0.2 mi. to station on the left or southerly side of road.

SKETCH



Reference Marks: (Proj. #2013)

A DCSO disk stamped "H 500 RM 1 1985" bears N 54°35'24" E, 17.55 ft. (grid) elev. 1029.513 ft.

A DCSO disk stamped "H 500 RM 2 1985" bears N 67°48'38" W, 24.75 ft. (grid) elev. 1029.131 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.