

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



H-020 28S 6W 4
Happy Valley Baseline D

NAD 558686.69 4142441.50
83 43°9'45" 123°25'11"

Station: "D" HAPPY VALLEY BASELINE T 28 S, R 6W, Sec 4

Set By (Agency): DCSO

Date Set: 1972

Recovered By RWS


Date Recovered 5-6-85

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



VERTICAL CONTROL *NGVD 29 CORPSON 6 NAVD 88 526,945 FT.*

Elevation: 523.500 ft. NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 2nd Agency: DCSO Proj. # 2013 Date: 1985

HORIZONTAL CONTROL *ocs 27 CS66/61*

South Zone State Plane Coordinates: Y(Northing) 558,721.81 X(Easting) 1,221,483.10

Precision: 1:25,000 Agency: DCSO Proj. # 2015 Date: 1990

Approximate Geographic Position: Latitude 43° 09' 45" Longitude 123° 25' 07"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "HAPPY VALLEY BASELINE D 1972" set in a 6" dia. concrete filled belltile approx. 1 ft. below surface of graveled shoulder.

TO REACH:

From the intersection of Carnes Rd. (Co. Rd. #16) and Happy Valley Rd. (Co. Rd. #26) in T28S, R6W, Sec. 2; proceed westerly along Happy Valley Rd. approx. 2.0 miles to monument on left.



Reference Marks:

A DCSO disk stamped "HAPPY VALLEY BASELINE STA D RM1" bears N53°E, 69.11' (geod.), elev. 522.705 ft.

A DCSO disk stamped "HAPPY VALLEY BASELINE STA D RM2" bears N55°W, 66.94' (geod.), elev. 523.461 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.