

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR



H-021 28S 6W 5  
Happy Valley Baseline E

NAD 558647.84 4139431.74  
83 43°9'43" 123°25'52"

VERTICAL CONTROL NGVD 29 CORPSCON 6 NAVD 88 557.478 FT

Elevation: 554.034 ft. NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2013 Date: 1985

HORIZONTAL CONTROL OCS 27 CS 66/b1

South Zone State Plane Coordinates: Y(Northing) 558,682.95 X(Easting) 1,218,473.34

Precision: 1:25,000 Agency: DCSO Proj. # 2015 Date: 1990

Approximate Geographic Position: Latitude 43° 09' 44" Longitude 123° 25' 48"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "HAPPY VALLEY BASELINE E 1972" set in a 6" concrete filled bell-tile approx. 1 ft. below the surface of graveled shoulder.

TO REACH:

From the intersection of Carnes Rd. (Co. Rd. #16) and Happy Valley Rd. (Co. Rd. #26) in T28S, R6W, Sec. 2; proceed westerly along Happy Valley Rd. approx. 2.5 miles to monument on left.



Reference Marks:

A DCSO disk stamped "HAPPY VALLEY BASELINE STA E RM1" bears S46°E, 33.30' (geod.), elev. 559.422 ft.

A DCSO disk stamped "HAPPY VALLEY BASELINE STA E RM2" bears S49°W, 34.28' (geod.), elev. 559.223 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.

