

OFFICE OF THE

DOUGLAS COUNTY SURVEYOR


h-035
HIGH

25S 4W 26

NAD
83

631958.98
43°22'13"

4219867.97
123° 8'18"



T 25 S, R 4W, Sec. 26

Station: HIGH

Set By (Agency): DCSO

Date: 1971

NAVD 29 2299

VERTICAL CONTROL CORPSCON 6 NAVD 88 2303 FT

Elevation: ~~2299.2~~ NGS(USC&GS) Line # _____ USGS Line # _____

Order Of Precision VA Agency: DCSO Proj. #: 2002 Date: 1971

HORIZONTAL CONTROL

OCS 27


Oregon State Plane Coordinates: Y(Northing) 631,994.19 X(Easting) 1,298,907.70 (South Zone)

Order Of Precision 1/100,000 Agency: DCSO Proj. #: 2002 Date: 1971

Approximate Geographic Position: Latitude= 43°22'13.9" Longitude= 123° 08' 14"

DESCRIPTION: High sta. lies on highest pt.
 of mtn. known as High Point. Sta. mark is
 a DCSO brass disk set in concrete filled 6"
 by 42" concrete bell tile projecting 8" above
 ground with underground mark 37" below ground,
 a DCSO brass disk, both marked "High 1971".
 For futher infromation see Douglas County
 Surveyor's Office records.

SKETCH



VICINITY: 5.5 mi. NW of Glide.

COMMENT: DESTROYED WAS NOTED ON THE COUNTER COPY OF THIS MONUMENT AT SOME POINT IN THE PAST, BUT WE CANNOT FIND ANY BACKUP TO PROVE THE NOTATION. NO MONUMENT VISIT SCHEDULED. 2/6/2009

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.