

Station: HEN - 5


T 22 S, R 8W, Sec 22

Date Set: 1998

Set By (Agency): DCSO


Date Recovered: 7-30-98

Recovered By: KWS SJF



H-074

- Found
- New
- Reset
- Not Found
- Referenced
- Destroyed



VERTICAL CONTROL

Elevation: 129.48 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 2007 Date: 1998

HORIZONTAL CONTROL CORPSCON6 NAVD88 133.05FT CS661052

South Zone O.C.S. 27: Y(Northing) _____ X(Easting) _____

South Zone O.C.S. 83: Y(Northing) 734765 X(Easting) 4090138

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approx. NAD 83 Geographic Position: Latitude 43° 38' 24" Longitude 123° 39' 22"

DESCRIPTION and TO REACH

2 3/4" DIA. DCSO DRILL CAP STAMPED "HEN-5 1998"
IS SET IN A 9" DIA CONCRETE FILLED PLASTIC
PIPE, PROTRUS 6" ABOVE GROUND

FROM THE INTERSECTION OF HENDERER ROAD
(CO. RD #118) AND MEHL CREEK RD (CO. RD #11)
IN T 22S R 7W SEC 30 PROCEED NORTHWESTERLY
ALONG HENDERER ROAD 3.75 MILE TO MONUMENT
ON RIGHT.

Reference Marks:

