

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Reported as Station: INGRAM B Destroyed 3/18/2025 T 27 S, R 5 W, Sec 19

Set By (Agency): DCSO

Date Set: 1980

Recovered By RS, SF


Date Recovered 3/13/84

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



1-009 275 5W 19
INGRAM B

NAD 576118.23 4164199.09
83 43°12'44" 123°20'26"

VERTICAL CONTROL **NGVD 29**

Elevation: 447.05 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # INGRAM BASELINE Date: 1980
(2007)

HORIZONTAL CONTROL **NAD 27**

South Zone State Plane Coordinates: Y(Northing) 576,153.44 X(Easting) 1,243,240.78

Precision: 1/20,000 Agency: DCSO Proj. # 2005-2 Date: 1980

Approximate Geographic Position: Latitude 43°12'45" Longitude 123°20'22"

DESCRIPTION and TO REACH

SKETCH


DESCRIPTION:

A DCSO disk stamped "INGRAM B 1980" set in a 6 in. dia. concrete filled tile flush with ground.

TO REACH:

From the intersection of Fowler St. and SE Douglas Ave. in Roseburg, proceed northerly 0.2 miles along Fowler St., past Justice hall, to an east-west running sidewalk on left; monument is approx. 160 ft. west along sidewalk, on right in lawn, south of Deer Creek and north of the Douglas County parking lot.

Reference Marks:



Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.