


DOUGLAS COUNTY SURVEYOR

NAD 753801.88 4206184.52  
83 43°42'12" 123°12'17"



T 21 S, R 4W, Sec. 32

Station: JULIE 1979

Set By (Agency): DCSO

Date: 1979

VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS(USC&GS) Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_

Order  
Of Precision \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. #: \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL

OCS 27


Oregon State Plane Coordinates: Y(Northing) 753,836.58 X(Easting) 1,285,223.57  
(South Zone)

Order  
Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1979

Approximate Geographic Position: Latitude= 43°42'12" Longitude= 123°12'12"

DESCRIPTION: A standard D.C. brass cap set in  
a conc. filled bell tile 6"x39" buried flush  
with ground. Approx. 365 ft. southerly of  
exit 162 Anlauf Lorane exit sign 35 ft. east of  
E.O.P. north lane I-5.

SKETCH



RM 1 N 16° 58' 56" E 75.04'

RM 2 S 58° 24' 46" E 79.07'

VICINITY: Approx. .9 miles north on I-5 from  
exit #160.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.