


OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: LINE T 27 S, R 2 W , Sec 12  
 Set By (Agency): DCSO  
 Date Set: 1981  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_



I-038  
LINE 27S 2W 12

NAD 579867.51 4288943.08  
 83 43°13'59" 122°52'23"



VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_


HORIZONTAL CONTROL NAD 27

South Zone State Plane Coordinates: Y(Northing) 579,904.09 X(Easting) 1,367,983.38  
 Precision: 1/25,000 Agency: DCSO Proj. # 2004-23 CS61/35 Date: 1982  
 Approximate Geographic Position: Latitude 43° 14' 00" Longitude 122° 52' 19"

DESCRIPTION and TO REACH

Station is a standard DCSO disk stamped "LINE 1981". Disk is set in a drill hole in a boulder flush with the ground.

To Reach: From the intersection of St. Hwy 138 and Co. Rd. 17 (Little River Rd.) west of Glide, proceed Southerly and Easterly along Co. Rd. 17 (it becomes FS 272) past Peel, Wolf Cr. Job Corps, and Emile Cr.. Continue on FS 272 almost to its intersection with FS 2703.



Reference Marks:

"LINE RM1 1981" is a standard DCSO disk set in concrete filled bell tile, flush with ground bears S74°57'23"W 49.43 ft. (grid) from the station.  
 "LINE RM2 1981" is a standard DCSO disk set in concrete filled bell tile, protruding 5" above the ground, bears S21°40'40"E 95.13 ft (grid) from the station.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.