



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR  
L-059



Station: LUTS-3 T 22 S, R 9 W, Sec 7  
Set By (Agency): DCSO  
Date Set: 1988  
Recovered By RWS, SJF  
Date Recovered 6/24/88  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_



VERTICAL CONTROL

Elevation: 75.272 ft. NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: 2nd order Agency: DCSO Proj. # 2007 Date: 1988

HORIZONTAL CONTROL CORPSCON6 NAVD88 78.85 FT.


South Zone State Plane Coordinates: Y(Northing) 745477 X(Easting) 4047011  
Precision: GIS SCALED Agency: DCSO Proj. # \_\_\_\_\_ Date: 2014  
Approximate Geographic Position: Latitude \_\_\_\_\_ Longitude \_\_\_\_\_

DESCRIPTION and TO REACH

A DCSO drill cap stamped "LUTS-3 1988" set in the ledge of a 10 ft. high rock outbank, approximately 1 ft. above road surface.

TO REACH:

From the intersection of State Hwy 38 and Lutsinger Creek Rd. in T22S, R9W, Sec.18, (near southwesterly end of bridge over Umpqua River at Scottsburg) proceed easterly along Lutsinger Creek Rd. approximately 1.8 miles to monument on right.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.