



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR



Station: N-9 T 29 S, R 5W , Sec 28  
Set By (Agency): USC&GS  
Date Set: 1920  
Recovered By RS, PB  
Date Recovered 11/8/83  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_



DESIGNATION N-001

VERTICAL CONTROL CORPSCON6 NAVD88 617.689 FT.

Elevation: 614.274 NGS Line # 6 USGS Line # \_\_\_\_\_ OSHD Line # 369, 1977  
Precision: 1st Agency: USC&GS Proj. # CS 66/43 Date: 1957

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 504529 X(Easting) 4172500  
Precision: GIS SCALED Agency: DCSO Proj. # \_\_\_\_\_ Date: 2014  
Approximate Geographic Position: Latitude 43° 01' 00" Longitude 123° 17' 58"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A disk stamped "N-9 1920 613.532 FT" set flush on SW concrete wing wall of SPRR bridge over South Umpqua River.

TO REACH:

Go to the SPRR bridge crossing of the South Umpqua River in T29S, R5W, Sec.28 near the City of Myrtle Creek.



NOTE: Due to the location, use of bench mark from I-5 would be difficult.  
CONCRETE WING WALL

Reference Marks:

7 3/4 FT. TO WEST RAIL

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.