


OFFICE OF THE

DOUGLAS COUNTY SURVEYOR

n-019  
NATURE

208 SW 15

NAD 83 544025.65 4152583.87  
43-23'51" 123°23'34"



T 25 S, R 6 W, Sec. 15

Station: NATURE

Set By (Agency): DCSO

Date: 1980

VERTICAL CONTROL

Elevation: 428.634 NGS(USC&GS) Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_

Order (Calapooya)  
Of Precision 2nd - I Agency: DCSO Proj. #: 2006 Date: 1981

HORIZONTAL CONTROL

Oregon State Plane Coordinates: Y(Northing) 644,060.26 X(Easting) 1,231,624.85  
(South Zone)

Order (Calapooya)  
Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1981

Approximate Geographic Position: Latitude= 43° 23' 51" Longitude= 123° 23' 32"

DESCRIPTION: Station mark is a standard DCSO

brass cap set in conc. filled belltile 6"

above ground - Cap is stamped "NATURE 1980".

Witness post and sign set in random NE-SW

fenceline bears West 7.5 ft., Co. Rd. r/w

5/8" I.R. #60+50 bears S64°W 17 ft., Co. Rd.

r/w 5/8" I.R. #59+50 bears N42°E 84.2 ft.

Station mark is West 70 ft. from centerline

of Co. Rd. #77.

VICINITY: From intersection of I-5 and Hwy 138  
go West 2.4 mi. on Hwy 138 to intersection of  
Hwy 138 and Co. Rd. #77. Proceed SW'ly 0.8  
mi. along Co. Rd. #77 to station on right cutbank.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.

SKETCH

