

write/rain

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: OLA-2


T 28S, R 7W, Sec 27

Date Set: 1999

Set By (Agency): DCSO


Date Recovered: 11-23-98

Recovered By: RWS SJF



0-023

- Found
- New
- Reset
- Not Found
- Referenced
- Destroyed



0-023

VERTICAL CONTROL

Elevation: 652.58 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 2007 Date: 1999

HORIZONTAL CONTROL CORPSCON6 NAVD88 656.041 CS 66/50
FT.

South Zone O.C.S. 27: Y(Northing) _____ X(Easting) _____

South Zone O.C.S. 83: Y(Northing) 539710 X(Easting) 4118453

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approx. NAD ²¹ Geographic Position: Latitude 43° 06' 28" Longitude 123° 30' 21"

DESCRIPTION and TO REACH

FROM THE INTERSECTION OF STATE HWY 42 AND OLALLA ROAD (CO. RD 38) INT 28S R7W SEC 27, PROCEED SOUTHERLY ALONG OLALLA ROAD 0.45 MILES TO MONUMENT ON LEFT.

A DCSO BRASS CAP STAMPED "OLA-2 1999" SET IN A 8" BY 42" LONG CONCRETE FILLED BELLTILE, PROTRUDES 2" ABOVE GROUND.

Reference Marks:

