



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: PTS-2 T 32 S, R 5 W, Sec 30  
 Set By (Agency): DCSO  
 Date Set: 1973  
 Recovered By RWS  
 Date Recovered 10/15/85  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_



NAI 411974.54 4157508.14  
 82 42945.41 120920.40

VERTICAL CONTROL

Elevation: 1467.821 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 412,010.66 X(Easting) 1,236,644.76  
 Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973  
 Approximate Geographic Position: Latitude 42°45'42" Longitude 123°20'36"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "PTS-2 1973" set in a 6 in. dia. concrete filled belltile flush with ground.

TO REACH:

From the intersection of Glendale access Rd. (exit 80) and I-5 in T32S,R6W,Sec.35, proceed northerly along I-5 approx. 1.95 miles to monument on right.



Reference Marks: (Proj. #2013)  
 A DCSO disk stamped "PTS-2 RM 1 1985" bears S 53°37'08" W, 42.66 ft. (grid) elev. 1467.339 ft.  
 A DCSO disk stamped "PTS-2 RM 2 1985" bears N 39°20'20" W, 39.66 ft. (grid) elev. 1468.105 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.