

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: PTS-15 T 31 S, R 5 W, Sec 24

Set By (Agency): DCSO

Date Set: 1975

Recovered By RS, JP


Date Recovered 9/14/83

Recovered By RWS, SJF

Date Recovered 10/28/85

Recovered By _____

Date Recovered _____



p-068
PTS-15

315 5W 24

NAD 445528.12 4184758.50
83 42°51'22" 123°14'51"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 445,564.22 X(Easting) 1,263,799.81

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1975

Approximate Geographic Position: Latitude 42°51'22" Longitude 123°14'46"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "PTS-15 1975"
set in a 6 in. concrete filled
tile flush with ground.

TO REACH:

From the intersection of I-5 and Co. Rd. #36
(Upper Cow Creek Rd. exit #88) in T32S, R5W,
Sec.11, proceed northerly along I-5 4.55 miles
to monument on right.



Reference Marks: (Proj. #2013)

A DCSO disk stamped "PTS-15 RM 1 1985"
bears N 32°10'29" E, 139.22 ft. (grid).

A DCSO disk stamped "PTS-15 RM 2 1985"
bears S 71°20'45" E, 34.25 ft. (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.