

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR


Station: PTS 101-14
 Set By (Agency): DCSO
 Date Set: 1975
 Recovered By GQ - TP
 Date Recovered 2-2-82
 Recovered By _____
 Date Recovered _____
 Recovered By _____
 Date Recovered _____

T 22 S, R 12W , Sec 5



p-093 22S 12W 5
 PTS-101-14

NAD 755872.33 3956149.99
 83 43°40'59" 124° 8'59"



VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____
 Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL


South Zone State Plane Coordinates: Y(Northing) 755,907.40 X(Easting) 1,035,189.31
 Precision: 1/15,000 Agency: DCSO Proj. # 6004-16 Date: 1975
 Approximate Geographic Position: Latitude 43°40'59" Longitude 124°08'54"

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO disk set in concrete tile stamped "PTS 101-14 1975". Monument is set flush with the ground.

To reach: From the intersection of 22nd Ave. & Hwy. 101 in Reedsport, proceed Southerly 1.5 mi. to turn out on the right (portion of old Hwy.) proceed right, down turn out. 0.1 mi. to monument on the left.



Monument to centerline of turnout road is 32 ft.

*Monument to survey marker sign on edge of turnout:

N42°W 16.0 ft.

Also another survey marker sign bears N 40° W, 2.5 ft.

Monument to 7" Fir bears S 70° W, 4.6 ft.

Monument to fog line Hwy 101 is 26 ft.

Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.