

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: R 615 T 31 S, R 5 W , Sec 2

Set By (Agency): OSHD

Date Set: 1966

Recovered By RWS, SIF


Date Recovered 1/29/85

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



r-014
R 615
31S 5W 2

NAD 460819.96 4184928.17
83 42°53'53" 123°14'55"

VERTICAL CONTROL NGVD 29

Elevation: 951.79 NGS Line # _____ USGS Line # _____ OSHD Line # 369

Precision: 3rd Agency: OSHD Proj. # _____ Date: 1980

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 460,855.95 X(Easting) 1,263,969.49

Precision: 1/25,000 Agency: DCSO Proj. # 2013 Date: 1985

Approximate Geographic Position: Latitude 42°53'53" Longitude 123°14'51"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

An OSHD disk stamped "R 615 1968" set flush in concrete walkway of Richie Rd. overcrossing of I-5.

TO REACH:

Go to the Richie Rd. overcrossing of I-5 (exit 95) in T31S,R5W,Sec.2, on southeast side near center of structure.



Reference Marks:

(Proj. #2013)

A DCSO brass stem in bridge decking (PTS-18)

bears S 36°42'21" W, 91.90 ft. (grid).

A DCSO disk stamped "PTS-18 RM 1 1985"

bears S 36°30'42" W, 39.18 ft. (grid) elev.952.43 ft. 3rd order.

A DCSO disk stamped "PTS-18 RM 2 1985"

bears S 54°32'43" W, 96.91 ft. (grid) elev. 935.16 ft. 3rd order.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.