

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: RAGS T 22 S, R 4 W, Sec 5

Set By (Agency): OSHD

Date Set: ?

Recovered By GQ,JP


Date Recovered 6/83

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



F-017
PAGE

358 84 5

NSD 743678.63 4807277.47
82 43°41'52" 123°11'10"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 748,728.33 X(Easting) 1,286,316.60

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1979

Approximate Geographic Position: Latitude 43°41'22" Longitude 123°11'55"

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION:

A OSHD disk stamped "DCSO RAGS 1979"
set in a concrete monument.

TO REACH:

Monument is approx. 2.0 miles south along
I-5 from Anlauf overcrossing of I-5, M.P. 160.6

Monument is 88 ft. Westerly of Southbound centerline
I-5; 65 1/2 ft., N 65°W, from Northerly end guardrail
West side I-5; 14 ft. Easterly from R/W fence; 6 ft.
lower than asphalt.

Reference Marks:

A DCSO disk stamped "RAGS RMI 1983"
bears N 33°53'04" E, 46.84 ft. (grid)

A DCSO disk stamped "RAGS RM2 1983"
bears S 27°08'43" W, 35.98 ft. (grid)

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.