

# Douglas County Geodetic Data Sheet


T 29 R 06 WS 08 A

Station: RC-3

Designation: R-099

Date Set: 1998 Set By (Agency): DCSO

Last Date Recovered: 12/00/2000



## VERTICAL CONTROL

NGVD 29 Elevation: 640.07 Feet

Precision: 3RD ORDER Agency: DCSO

CS File: 66055

Date: 1998

NAVD 88 Elevation: 643.53 FT.

Precision: CORPSCON6 Agency: NAVD88

CS File:

Date:

## HORIZONTAL CONTROL

OCS 27 Y(Northing): X(Easting): Lat 43° 03' 48.9" Long: 123° 25' 29.6"

Precision: GIS Agency: CS File: Date:

OCS 83 Y(Northing): 522677 X(Easting): 4139562 Lat Long:

Precision: GIS SCALED Agency: DCSO CS File: Date: 2014

OCS 83/91 Y(Northing): X(Easting): Lat Long:

Precision: Agency: CS File: Date:

OCS 83/98 Y(Northing): X(Easting): Lat Long:

Precision: Agency: CS File: Date:


Description: Scaled Lat 43° 03' 49" Long: 123° 25' 30"

A 2 7/8 INCH DIAMETER DCSO DRILL CAP STAMPED; RC-3 1998; SET FLUSH IN TOP OF AN 8X42 INCH CONCRETE FILLED BELL TILE SET PROTRUDING APPROX. 4 INCHES ABOVE GROUND NEAR EDGE AT TOP OF FILL SLOPE.

## Comments:

FROM THE INTERSECTION OF WILLIS CREEK RD; CO RD NO. 43; AND RICE CREEK RD; CO. RD NO. 43A; IN T29S R6W SEC 4 PROCEED SOUTHERLY ALONG RICE CREEK RD APPROX 1.55 MILES TO MONUMENT ON LEFT.

## Notes:



Note: For further information contact the Douglas County Surveyors Office, Room 105A Douglas County Courthouse, Roseburg, OR 97470. Phone 440-4272 or Fax (541)957-8150. Douglas County Residents outside Roseburg calling area, dial toll free 1-800-224-1619.