

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: S 10 T 24 S, R 5W, Sec 20

Set By (Agency): USGS

Date Set: 1903

Recovered By LEM



Date Recovered 12/77

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



s-013  
S 10

NAD 667930.01 4173938.36  
83 43°27'54" 123°18'56"

VERTICAL CONTROL NGVD29

Elevation: 465.130 NGS Line # 6 USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 1st Agency: USC&GS Proj. # \_\_\_\_\_ Date: 1957

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 667,964.41 X(Easting) 1,252,978.79

Precision: 1/25,000 Agency: DCSO Proj. # 2010-4 C.S.59/47 Date: 1978

Approximate Geographic Position: Latitude 43° 27' 54" Longitude 123° 18' 52"

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION:

Monument is a bronze disk stamped  
"S 10 464 1903" set in concrete  
post.

**Abridged version  
keyed into SARS.**

TO REACH:

Monument is approx. 3.7 mi. north of  
Oakland along the SPRR from the station  
at Oakland.

From the intersection of Co. Rd. #29  
(Goodrich Rd.) and SPRR in T24S, R5W,  
Sec.20, proceed southerly along SPRR  
0.25 miles.

Monument is approx. 115 yds. south  
a culvert at SPRR mile point 592.70,  
15.5 ft. NE of a telephone pole with  
a guv wire, and 1.9 ft. W. of a fence.

Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.