

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: S-15 T 21 S, R 10W, Sec 6

Set By (Agency): DCSO

Date Set: 1973

Recovered By GO-TP


Date Recovered 1-28-82

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



S-018
S-15
215 10W 6

NAD 788357.99 4013906.28
83 43°46'43" 123°56'11"

S-018

VERTICAL CONTROL **NAD 29**

Elevation: 12.308 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL **NAD 27**

South Zone State Plane Coordinates: Y(Northing) 788,393.57 X(Easting) 1,092,945.94

Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973


Approximate Geographic Position: Latitude 43°46'44" Longitude 123°56'07"

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO disk set in concrete tile protruding 2" above the ground stamped "S-15 1973".

To reach: From the intersection of Co. Rd. 48A & Rd. #48 (in sec. 31 T20S R10W) proceed easterly along Rd. #48 1.45 miles to a private gravel road on the right (in sec. 32 T20S R10W), proceed southerly along private road 0.95 miles to locked International Paper Co. gate. Proceed thru gate 2.1 miles along private road to monument on the right.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.