

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR


Station: S 444 T 28 S, R 6 W , Sec 21  
 Set By (Agency): OSHD  
 Date Set: 1952  
 Recovered By RS, SJF  
 Date Recovered Oct. 24, 1984  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_



s-028  
S 444

28S 6W 21

NAD 541045.52 4142723.42  
83 43° 6'51" 123°24'59"



VERTICAL CONTROL NGVD 29

Elevation: 528.250 ft. NGS Line # 6 USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: 1st. Agency: USC&GS Proj. # \_\_\_\_\_ Date: 1957

HORIZONTAL CONTROL OCS 21

South Zone State Plane Coordinates: Y(Northing) 541,080.66 X(Easting) 1,221,765.14  
 Precision: 1/25,000 Agency: DCSO Proj. # 2008-2013 Date: 1984  
 Approximate Geographic Position: Latitude 43°06'51" Longitude 123°24'55"


DESCRIPTION and TO REACH

An OSHD disk stamped "S 444 1952" set flush in the northwest corner of northwest sidewalk of highway bridge over the South Umpqua River.

TO REACH:

From the intersection of State Highway 99 and Thompson Ave. (Co. Rd. 266) in Winston, T28S, R6W, Sec. 21, proceed southwesterly approx. 0.1 miles along State Highway 99 to bridge over South Umpqua River and monument on right.

SKETCH



Reference Marks:

A OSHD disk stamped "R 444 1952" bears S 27°11'45" W, 505.44 ft. (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.



10.24.2005