

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: SADDLE T 28 S, R 6 W, Sec 27

Set By (Agency): Don Garrett  
L.S. #0544

Date Set: 1972

Recovered By SJF



Date Recovered May 18, 1984

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



NAD 534808.32 4146783.92  
83 43° 6' 10" 123° 24' 3"

VERTICAL CONTROL **NGVD 29**

Elevation: 1308.3 ft. NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: v/a Agency: Don Rentz Proj. # \_\_\_\_\_ Date: 1972

HORIZONTAL CONTROL **OCS 27** L.S. #0839

South Zone State Plane Coordinates: Y(Northing) 536,843.50 X(Easting) 1,225,825.63

Precision: 1/25000 Agency: DCSO Proj. # 2005 C.S. 56/9 Date: 1972

Approximate Geographic Position: Latitude 43°06'11" Longitude 123°23'59"


DESCRIPTION and TO REACH

A 3 inch DCSO disk on a 2 inch iron pipe, stamped "SADDLE 1972" and protruding 4 inches from the ground.

TO REACH:

From the intersection of Dole Rd. (Co. Rd. #14 ) and Roberts Mountain Rd. ( Co. Rd. #123) in T29S,R6W,Sec.1, proceed northerly along Roberts Mountain Rd. approximately 2.6 miles to unpaved private road on right. ( Locked gate; to obtain key, contact Roseburg Lumber) Proceed southwesterly along unpaved private road approximately 0.85 miles to fork; take right fork, proceed southwesterly approx. 0.15 miles to fork in road; take right fork, proceed northwesterly approx. 150 ft. to fork in road; take left fork, proceed westerly approx. 0.35 miles to fork in road at ridge saddle; follow right fork westerly approximately 150 feet beyond west end of saddle bottom, to monument on right. Monument lies north of east-west fenceline near top of steep north slope.

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.