



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR



Station: SNERDLY  
 Date Set: 1991  
 Set By (Agency):- DCSO  
 Date Recovered: 3/8/91  
 Recovered By: SJF,TF  
 Date Recovered: \_\_\_\_\_  
 Recovered By: \_\_\_\_\_  
 Date Recovered: \_\_\_\_\_  
 Recovered By: \_\_\_\_\_

T 28 S, R 4 W , Sec 23



DESIGNATION S-147

VERTICAL CONTROL

Elevation: 1,018.344 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2007 Date: 1991

HORIZONTAL CONTROL CORPSCON6 NAVD88 1021.873 FT CS 66/43

South Zone O.C.S. 27: Y(Northing) \_\_\_\_\_ X(Easting) \_\_\_\_\_

South Zone O.C.S. 83: Y(Northing) 539097 X(Easting) 4216135

Precision: GIS SCALED Agency: DCSO Proj. # \_\_\_\_\_ Date: 2014


Approx. NAD <sup>83</sup><sub>27</sub> Geographic Position: Latitude 43°06'55" Longitude 123°08'26"

DESCRIPTION and TO REACH

SKETCH

A DCSO disk stamped "SNERDLY 1991" set in a 8"x40" concrete filled belltile protruding 2" above ground.

From the intersection of North Myrtle Rd. (Co.Rd.#15) and Slide Creek Rd. (Co.Rd.#149) in T28S,R4W,Sec.33, proceed northeasterly along North Myrtle Rd. 2.75 miles to monument on right.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.