

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: TIGGER
 Set By (Agency): DCSO
 Date Set: 1980
 Recovered By RWS, SJF
 Date Recovered 12/01/88
 Recovered By _____
 Date Recovered _____
 Recovered By _____
 Date Recovered _____


T 25 S, R 6 W , Sec 30



t-036
TIGGER

25S 6W 30

NAD 683594.23 4136116.39
 88 43°22' 21" 123°27'12"



VERTICAL CONTROL

Elevation: 389.57 ft. NGS Line # _____ USGS Line # _____ OSHD Line # _____
 Precision: 3rd Agency: DCSO Proj. # 2006 Date: 1981

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 633,628.93 X(Easting) 1,215,157.56
 Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1981
 Approximate Geographic Position: Latitude 43°22'02" Longitude 123°27'08"


DESCRIPTION and TO REACH

SKETCH

A DCSO disk stamped "TIGGER 1980" set in a 6 in. dia. concrete filled concrete tile protruding approx. 4 in. above ground.

TO REACH:

Go to the intersection of Fort McKay Rd.
 (Co.Rd.#9) and Tyee Rd. (Co.Rd.#33)
 in T25S,R6W,Sec.30.



Reference Marks:

A DCSO disk stamped "TIGGER RM 1 1980" bears S 61°19'13" E, 58.50 ft. (grid) 3rd order elevation 386.36 ft.

A DCSO disk stamped "TIGGER RM 2 RESET 1988" bears S 32°17'43" W, 79.19 ft. (grid), 3rd order elevation 378.44 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.