

2/82


OFFICE OF THE

t-039
TIMBER

22S 5W 9

DOUGLAS COUNTY SURVEYOR

NAD 745653.85 4180309.81
83 43°40'43" 123°18' 5"



T-039

VERTICAL CONTROL

T 22 S, R 5W, Sec. 9

Station: TIMBER

Set By (Agency): DCSO

Date: 1979

Elevation: _____ NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision _____ Agency: _____ Proj. #: _____ Date: _____

HORIZONTAL CONTROL

NAD 27

Oregon State Plane Coordinates: Y(Northing) 745,688.68 X(Easting) 1,259,349.13
(South Zone)

(North County)


Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1979

Approximate Geographic Position: Latitude= 43° 40' 44" Longitude= 123° 18' 01"

DESCRIPTION: A standard DCSO brass cap set in conc. and iron filled bell tile 6"x39" buried 35" in the ground, 36.5 ft., S 60° E, to ctr. of SPRR, 9 ft., N 28° E, to edge of pavement of Co. Rd. #68, survey marker on RR crossing sign 23 ft.

A DCSO disk stamped "TIMBER RM 1 1979", set flush with ground bears N 7° 54' 34" W 81.54' (grid)
A DCSO disk stamped "TIMBER RM 2 1979", set 5" below surface bears S 77° 25' 38" E 142.36' (grid)

SKETCH



VICINITY: 1.25 miles northerly from Drain on

Hwy. 99 to Co. Rd. #68 (Laurel Hill Dr.)

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.