

12/82


OFFICE OF THE

u-007  
U-7 RESET

25S 7W 22

DOUGLAS COUNTY SURVEYOR

NAD 638949.87 4118838.71  
83 43°22'49" 123°31' 9"



T 25 S, R 7W, Sec. 22

Station: U-7 1972 RESET 1976

Set By (Agency): DCSO

Date: 1976

U-007

VERTICAL CONTROL

NGVD29

Elevation: 343.965 NGS(USC&GS) Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_

Order  
Of Precision 2nd Agency: DCSO Proj. #: 2006 Date: 1976

HORIZONTAL CONTROL

NAD 27

Oregon State Plane Coordinates: Y(Northing) 638,984.48 X(Easting) 1,197,879.81  
(South Zone)

Order  
Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1976

Approximate Geographic Position: Latitude= 43° 22' 49" Longitude= 123° 31' 04"

DESCRIPTION: A STANDARD DOUGLAS COUNTY

SURVEYORS OFFICE BRONZE DISK SET IN A

DRILL HOLE IN A SANDSTONE BOULDER, LEVEL

WITH THE ROADWAY. 23 FT. FROM THE CENTER-

LINE OF CO. RD. #33, 11 FT. N.E. OF THE


S'THLY R/W FENCE MARKED "U-7 1972 RESET

1976".

VICINITY: FROM THE INTERSECTION OF FORT MCKAY RD.

(Co. Rd. #9) AND TYEE RD. (Co. Rd. #33) PROCEED NW'LY ALONG TYEE RD. 3.6 MI. TO MON. ON LEFT.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.