

2/82

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

U-114 255 SW 18
UMPQUA NE BASE

NAD 642916.67 4168901.46
83 43°23'45" 123°19'53"


T 25 S, R 5W, Sec. 18

Station: UMPQUA NE BASE

Set By (Agency): DCSO

Date: 1971

4/95 FD OK per BENTZ 1995-0050



U-114

VERTICAL CONTROL

NGVD 29
Elevation: ~~674.8~~ 675 NGS(USC&GS) Line # _____ USGS Line # _____

Order (Rsbg. Primary Net)
Of Precision VA Agency: DCSO Proj. #: 2002 Date: 1971

HORIZONTAL CONTROL

NAD 27
Oregon State Plane Coordinates: Y(Northing) 642,952.70 X(Easting) 1,247,940.34
(South Zone)

Order (Rsbg. Primary Net)
Of Precision 1/25,000 Agency: DCSO Proj. #: 2002 Date: 1971

Approximate Geographic Position: Latitude= 43° 23' 46" Longitude= 123° 19' 49"


DESCRIPTION: BRASS DISK SET IN CONCRETE
FILLED 6" X 42" BELL TILE 6" ABOVE GROUND
WITH UNDERGROUND MONUMENT IN CONCRETE.

Witness sign 2 ft. West of station stamped
"Umpqua N.E. Base 1971"

To reach: From intersection of Central Ave.
and Comstock Rd. proceed N'thly on Comstock
Rd. 0.55 mi. to station on W'stly side of
road.

VICINITY: WEST OF COMSTOCK ROAD.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.