

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: VIC. T 30 S, R 3W, Sec 26

Set By (Agency): DCSO

Date Set: 1975

Recovered By JP-RWS

Date Recovered 3-18-82

Recovered By RWS, S.J.F.

Date Recovered 8/14/85


Recovered By RWS - 5/29/98 FO OK

Date Recovered \_\_\_\_\_



v-022  
VIC 305 3W 26

NAD 474301.35 4244908.33  
83 42°56'24" 123° 1'35"



VERTICAL CONTROL NGVD 29

Elevation: 953.355 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2010-2 Date: 1975

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 474,337.54 X(Easting) 1,323,949.82

Precision: 1/25,000 Agency: DCSO Proj. # 2010-2 Date: 1975


Approximate Geographic Position: Latitude 42°56'25" Longitude 123°01'31"

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO disk stamped "Vic 1975" set in concrete filled hole in rock, flush with the ground and approx. 10 ft. above the surface of the road. Witness sign and post bear South 3 ft.

To reach: From the junction of State Hwy. 227 and BLM Rd. T30-3-26.0 (Corn Creek) proceed Easterly 0.15 miles to station on the right or the Southerly side of the road.



Reference Marks: (Proj. #2013)  
A DCSO disk stamped "VIC RM 1 1985" bears N89°03'04" E, 34.74 ft. (grid) elev.950.091  
~~A DCSO disk stamped "VIC RM 2 1985" bears N 0°00'10" E, 91.60 ft. (grid).~~  
**RM 2 NOT FOUND 9/98**

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.