



Station: V248
Date Set: 1937
Set By (Agency): OSHD
Date Recovered: 11/5/96
Recovered By: SOF

T 28 S, R 6W, Sec 11



V-037

VERTICAL CONTROL NGVD 29

Elevation: 518.085 FL NCS Line # _____ USGS Line # _____ OSHD Line # 6

Precision: 1ST ORDER Agency: USCGS Proj. # _____ Date: 1957

HORIZONTAL CONTROL CORPSCON6 NAVD88 521.538 FT.

South Zone O.C.S. 27: Y(Northing) _____ X(Easting) _____

South Zone O.C.S. 83: Y(Northing) 554140 X(Easting) 4154926

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approx. NAD ²⁷ Geographic Position: Latitude 43°09'05" Longitude 123°22'17"

TOPO ZONE

DESCRIPTION and TO REACH

A 3 INCH DIAMETER STATE HIGHWAY DEPARTMENT
DISK STAMPED "1937 517 V248" SET IN THE SOUTH END OF
WEST ABUTMENT WALL OF LARGE BOX CULVERT UNDER OLD HIGH-
WAY 99; APPROXIMATELY 2 FEET LOWER THAN ROAD SURFACE.

FROM THE INTERSECTION OF STATE HIGHWAY 42 AND OLD HIGH-
WAY 99 IN T28S, R6W, SECTION 11 PROCEED NORTHERLY ALONG OLD HIGH-
WAY 99 APPROXIMATELY 500 FEET TO MONUMENT ON LEFT.

Reference Marks:

