

OFFICE OF THE

DOUGLAS COUNTY SURVEYOR


W-01E
W 675

01E 5W 34

WAL
EE

783174.81
48°01'39"

4166049.45
123°16'42"



T 21 S, R 5W, Sec. 34

Station: W 675

Set By (Agency): OSHD

Date: 1978

VERTICAL CONTROL

Elevation: 331.629 NGS(USC&GS) Line # 6 USGS Line # _____

Order Of Precision 3rd Agency: OSHD Proj. #: _____ Date: 1978

HORIZONTAL CONTROL


Oregon State Plane Coordinates: Y(Northing) 753,179.32 X(Easting) 1,265,383.65
(South Zone)

Order Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1979
(North County)

Approximate Geographic Position: Latitude= 43°42'00" Longitude= 123°16'42"

DESCRIPTION: A bronze disk set at finished
deck grade in the NE corner of highway structure
over Sand Creek 20 ft. from centerline Hwy.
99 and 0.3 ft. from bridge rail.

SKETCH



VICINITY: 3.35 mi. North of Drain Post

Office. on Hwy. 99

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.