



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



W-021

Station: WC SW -S T 28 S, R6W , Sec 20
 Set By (Agency): DCSO
 Date Set: 1985
 Recovered By JL, RWS, SJF
 Date Recovered 3-4-85
 Recovered By _____
 Date Recovered _____
 Recovered By _____
 Date Recovered _____



VERTICAL CONTROL NGVD 29

Elevation: 524.409 ft. NGS Line # _____ USGS Line # _____ OSHD Line # _____
 Precision: 2nd Agency: DCSO Proj. # 2013 Date: 1985

HORIZONTAL CONTROL CORPSCON6 NAVD88 527.845 FT. CS 66/61

South Zone State Plane Coordinates: Y(Northing) 542448 X(Easting) 4136266

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approximate Geographic Position: Latitude 43°07'02" Longitude 123°26'21"

DESCRIPTION and TO REACH

DESCRIPTION:

A 4" x 5 1/2" iron plate with raised letters "WEST COAST STEEL WORKS PORTLAND OREGON 1959" set flush in the south east corner of a concrete bridge.

TO REACH:

From the intersection of (Co. Rd. #47) (Brockway-Lookingglass) and State Hwy. #42 in T28S, R6W, Sec. 29; proceed northerly along Co. Rd. #47 approx. 0.35 miles to bridge over Lookingglass Creek and monument in southeast corner.

*Note elevation taken over "5" in 1959.

Reference Marks:

A DCSO disk stamped "WEST COAST STEEL WORKS PORTLAND OREGON 1959" elev. taken over "5" bears N40°E, 283' (geod.), elev. 524.455 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.

