



Date Set: 1999

Set By (Agency): DCSO

Date Recovered: JUNE 30, 1999

Recovered By: RWS, SJF

- Found
- New
- Reset
- Not Found
- Referenced
- Destroyed



DESIGNATION W-071

VERTICAL CONTROL

Elevation: 773.12 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 2007 Date: 1999

HORIZONTAL CONTROL CORPSCON6 NAVD88 776.69 FT. CS66156

South Zone O.C.S. 27: Y(Northing) _____ X(Easting) _____

South Zone O.C.S. 83: Y(Northing) 594888 X(Easting) 4238274

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approx. ^{OC527} ~~NAD 83~~ Geographic Position: Latitude 43° 16' 13" Longitude 123° 03' 50"

DESCRIPTION and TO REACH

A 2 3/8 INCH DIAMETER DCSO DRILL CAP STAMPEN
"WHISKERS 1999" SET FLUSH IN TOP OF 2 1/2 FOOT DIAMETER
EXPOSED PORTION OF LARGE BOULDER JUST OFF OF SOUTHERLY
ROAD SHOULDER.

FROM THE INTERSECTION OF BUCKHORN RD (CO. RD. # 17)
AND LITTLE RIVER RD. (CO. RD. # 17C) IN T26S, R3W, SECTION 30
PROCEED 2.0 MILES SOUTHEASTERLY ALONG LITTLE RIVER RD.
TO MONUMENT ON RIGHT. THIS MONUMENT IS APPROXIMATELY
450' NORTHWESTERLY FROM DRIVEWAY TO 3220 AND 3778
LITTLE RIVER ROAD.

Reference Marks:

