

PLSS 174100

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: WC to SE COR SEC 31 T 21 S, R 11W , Sec 31

Set By (Agency): DCSO

Date Set: 1971

Recovered By DCSO


Date Recovered 1973

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



210-11W-31-018 21S 11W 31
WC TO SE COR SEC 31

NAD 758,211.78 3,982,209.02
83 43°41'33" 124° 3' 6"

VERTICAL CONTROL *NGVD 29*

Elevation: 9.188 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL *NAD 27*

South Zone State Plane Coordinates: Y(Northing) 758,246.90 X(Easting) 1,061,248.62

Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973

Approximate Geographic Position: Latitude 43° 41' 33" Longitude 124° 03' 01"

DESCRIPTION and TO REACH

SKETCH

Brass cap on Township line 414.35 ft. West of Sec. corner flush with ground on highway shoulder marked "County Surveyor's Office 1971 T21S R11W R1 S31 S6 T22S". This cap lies on south edge of highway 7.0 ft. South and 9.0 ft. East of edge of pavement

Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.