

PLSS ~~500140~~
500140

210-12W-34-021
E 1/4 CORNER

21S 12W 34

OFFICE OF THE

DOUGLAS COUNTY SURVEYOR

NAD
83

763247.43
43°42'17"


3968642.98
124° 6'13"

T 21 S, R 12W, Sec. 34

Station: E 1/4 CORNER

Set By (Agency): U.S.A.C.E.

Date: 1966



VERTICAL CONTROL

Elevation: _____ NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision _____ Agency: _____ Proj. #: _____ Date: _____

HORIZONTAL CONTROL

Oregon State Plane Coordinates: Y(Northing) 763,282.55 X(Easting) 1,047,682.55
(South Zone)

Order
Of Precision 1/5,000 Agency: DCSO Proj. #: _____ Date: 1979

Approximate Geographic Position: Latitude= 43°42'17" Longitude= 124°06'09"


DESCRIPTION: Station mark is an Army Corps of Engineers brass cap marked "T21S R12W 1/4 S34 | S35".

Monument is 3 1/2" diameter and flush with ground.

Cap is marked, and oriented to the East. A witness post and sign bears 1 ft. South. Station mark is in fill area on South side of Hwy. 101 at Westerly end of bridge over the Umpqua River at Reedsport.

VICINITY: Reedsport

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.