

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: COX  
Set By (Agency): OSHD  
Date Set: ?  
Recovered By GQ, JP  
Date Recovered 6/83  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_


T 22 S, R 4 W, Sec 19



c-113  
COX

225 4W 19

NAD 729126.83 4201858.13  
83 43°38' 7" 123°13' 5"



VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 729,161.45 X(Easting) 1,280,897.59  
Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1979  
Approximate Geographic Position: Latitude 43°38'07" Longitude 123°13'00"  
C.S. 60/23

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION:

A OSHD disk stamped "COX 1979"  
set in SW corner of sidewalk.

TO REACH:

Monument is 6.1 miles south of  
Curtin on I-5 at Cox Rd. overcrossing.

Reference Marks:

A DCSO disk stamped "COX RML 1983"  
bears N 14°52'06" E, 27.34 ft. (grid)

A DCSO disk stamped "COX RM2 1983"  
bears S 69°58'31" E, 155.00 ft. (grid)

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.