


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: ELK
Set By (Agency): DCSO
Date Set: 1978
Recovered By GQ,JP
Date Recovered 6/83
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____

T 22 S, R 4 W , Sec 30



NAD 727398.36 4201292.70
63 43°37'50" 123°13'12"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 727,430.87 X(Easting) 1,280,332.39
Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1978
Approximate Geographic Position: Latitude 43°37'50" Longitude 123°13'07"

DESCRIPTION and TO REACH

SKETCH


C.S. 60/23

DESCRIPTION:

A DCSO disk stamped "ELK 1978"
set in a concrete filled belltile
8 in. under ground.

TO REACH:

Monument is 6.5 miles south of
Curtin on I-5, 0.4 miles south
of Cox Rd. overcrossing I-5.



Reference Marks:

A DCSO disk stamped "ELK RM1 1983"
bears S 7°25'59" W , 28.23 ft. (grid)

A DCSO disk stamped "ELK RM2 1983"
bears N 76°42'34" W, 13.35 ft. (grid)

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.