


OFFICE OF THE


J-019
JAWS

22S 12W 7

DOUGLAS COUNTY SURVEYOR

NAD
83753876.66
43°40'36"3948926.00
124°10'36"T 22 S, R 12 W, Sec. 7Station: JAWSSet By (Agency): DCSODate: 1980VERTICAL CONTROL NGVD 29Elevation: 9.615 NGS(USC&GS) Line # _____ USGS Line # _____Order
Of Precision 2nd Agency: DCSO Proj. #: 2007 CS 61/16 Date: 1981HORIZONTAL CONTROL NAD 27Oregon State Plane Coordinates: Y(Northing) 753,911.68 X(Easting) 1,027,965.33
(South Zone)Order
Of Precision 1/15,000 Agency: DCSO Proj. #: 2008 Date: 1980Approximate Geographic Position: Latitude= 43° 40' 36" Longitude= 124° 10' 31"DESCRIPTION: Station mark is a standardDouglas County Surveyor's Office 3" diam.brass cap stamped "JAWS 1980". Cap isset in drill hole in concrete curb on Westside of Beach Blvd. 223 ft. Southof intersection with 7th St. See sketch.VICINITY: Winchester Bay - Salmon Harbor

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.