



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: X554 T 23 S, R 5 W , Sec 10
Set By (Agency): USC&GS
Date Set: 1954
Recovered By RWS,SJF
Date Recovered 9/11/87
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____



X-012
X 554

NAD 709483.04 4185349.06
83 43°34'48" 123°16'40"

X-012
VERTICAL CONTROL NGVD 29

Elevation: 373.067 NGS Line # 6 USGS Line # _____ OSHD Line # _____
Precision: 1st Agency: USC&GS Proj. # _____ Date: 1956

HORIZONTAL CONTROL NAD 27

South Zone State Plane Coordinates: Y(Northing) 709,517.61 X(Easting) 1,264,388.85
Precision: 1/25,000 Agency: DCSO Proj. # 2010-6,CS60/23 Date: 1978

Approximate Geographic Position: Latitude 43°34'48" Longitude 123°16'36"


DESCRIPTION and TO REACH

SKETCH

A USC&GS disk stamped "X554 1954" set in
a 10 in. dia. concrete post protruding
4 in. above ground.

TO REACH:

From the intersection of State Hwy 99 and
Wilson Rd. (Co.Rd.#127) in T23S,R5W,Sec.10,
proceed easterly along Wilson Rd. 0.15 miles
to monument on left.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.