



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: W 1/4 PLSS 300340
Set By (Agency): Prof. Eng. #2128 T 24 S, R 5 W, Sec 21
Date Set: 1977
Recovered By RWS, SJF
Date Recovered September, 1987
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____



W 1/4 CORNER
NAD 669096.05 4176308.11
83 43°28' 6" 123°18'25"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL

NAD 27
South Zone State Plane Coordinates: Y(Northing) 669,130.35 X(Easting) 1,255,348.43
Precision: 1/2 ~~5,000~~ Agency: DCSO Proj. # 2010-4 CS59/47 Date: 1978
Approximate Geographic Position: Latitude 43°28'07" Longitude 123°18'20"

DESCRIPTION and TO REACH

SKETCH

See Douglas County Surveyor records
of Government corners renewed.

Reference Marks:

A DCPW disk stamped " BM-2 1977" set in a 6 inch diameter concrete filled plastic pipe protruding 2 inches above ground bears S79°40'30"E, 202.04 feet distant (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.