

Douglas County Geodetic Data Sheet


Station: TRUCKS

Designation: T-053

T 24 R 05 S 34

Date Set: 1980 Set By (Agency): DCSO

Last Date Recovered:



VERTICAL CONTROL

NGVD 29 Elevation: 526.069 Feet

Precision: 2ND-I Agency: DCSO

Project: 2006

Date: 1981

NAVD 88 Elevation: Meters

Precision: Agency:

Project:

Date:

NGS Line # USGS Line #

OSHD Line #

File #

HORIZONTAL CONTROL

OCS 27 Y(Northing): 655,779.72 X(Easting): 1,263,354.71 Lat:

Long:

Precision: 1/25,000 Agency: DCSO

Project: 2006

Date: 1981

OCS 83 Y(Northing): 655,745.20 X(Easting): 4,184,314.11 Lat: 43°25'57"

Long: 123°16'30"

Precision: Agency:

Project:

Date:

OCS 83/91 Y(Northing): X(Easting): Lat:

Long:

Precision: Agency:

Project:

Date:

OCS 27 Scaled Latitude: 43°25'57"

OCS 27 Scaled Longitude: 123°16'26"


DESCRIPTION:

A STANDARD DCSO BRASS CAP SET IN A 6X36 INCH CONCRETE FILLED BELLTILE STAMPED; TRUCKS 1980; PROTRUDING 3 INCHES FROM THE GROUND.

COMMENTS:

18 FT TO EDGE OF PAVEMENT OF CO RD 22 AND
5 FT ABOVE ROAD BED. 9.5 FT TO PP 3H 62
BEARING N54W 1.7 FT TO WITNESS POST AND
2.7 FT TO FENCE. VICINITY - APPROX 1.3 MILES
FROM THE INTERSECTION OF OAK AND OLD
HWY 99 IN THE TOWN OF OAKLAND.

SKETCH



Note: For further information contact the Douglas County Surveyors Office, Room 105A Douglas County Courthouse, Roseburg, OR 97470. Phone 440-4272 or Fax (541)957-8150. Douglas County Residents outside Roseburg calling area, dial toll free 1-800-224-1619.