


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

S-072
SEEDS

25S 5W 7

NAD 649976.28 4165002.93
83 43°24'53" 123°20'49"



T 25 S, R 5 W, Sec. 7

Station: SEEDS

Set By (Agency): DCSO

Date: 1980

S-072

VERTICAL CONTROL

NGVD 29

Elevation: 435.855 NGS(USC&GS) Line # _____ USGS Line # _____

Order (Calapooya)
Of Precision 2nd-I Agency: DCSO Proj. #: 2006 Date: 1981

HORIZONTAL CONTROL

NAD 27
Oregon State Plane Coordinates: Y(Northing) 650,010.83 X(Easting) 1,244,043.74
(South Zone)

Order (Calapooya)
Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1981

Approximate Geographic Position: Latitude= 43° 24' 54" Longitude= 123° 20' 45"

DESCRIPTION: A standard DCSO brass cap set
in a conc. filled 6"x42" belltile buried 38"
in the ground on a 15.0 ft. high cut bank;
15.4 ft. above pavement Co. Rd. 23, 38.5 ft.
North of centerline of Co. Rd. 23, 13.5 ft. South
of Northerly R/W fence, approx. 400.0 ft. SW
along Co. Rd. 23 from Doug. Elect. power station.

TO REACH: From the intersection of Hwy 99 and
Locust proceed N'ly along Hwy 99 to Co. Rd. 23.
Go Westerly approx. 2.35 mi. to mon. on right
(top of cutbank) monument is approx. 1.4 mi. from
overpass of I-5 to station "SEEDS".

VICINITY: approx. 1.4 mi. SW of I-5 Hwy on Green
Valley Rd. (Co. Rd. 23) West of Oakland.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.

SKETCH

