


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

n-022
FADED

258 6W 23

NAD 83 583453.77 4145831.91
43°22'23" 123°25'27"



T 25 S, R 6 W, Sec. 28

Station: PADDON

Set By (Agency): DCSO

Date: 1980

VERTICAL CONTROL

Elevation: 401.704 NGS(USC&GS) Line # _____ USGS Line # _____

Order Of Precision 2nd - II Agency: DCSO Proj. #: 2006 (Calapooya) Date: 1981

HORIZONTAL CONTROL

Oregon State Plane Coordinates: Y(Northing) 635,498.45 X(Easting) 1,222,872.99
(South Zone)

Order Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 (Calapooya) Date: 1981


Approximate Geographic Position: Latitude= 43° 22' 24" Longitude= 123° 25' 24"

DESCRIPTION: Station mark is a standard DCSO
brass cap set in a 6" diam. conc. tile filled
with conc. and buried with top of mon. flush
with ground. Centerline of Co. Rd. #9 is 30'
N'thly; center of driveway at pavement edge
is 63' E'stly; telephone box #113 bears N27°E
106.5'. Set witness post and sign in S'thly
r/w fence 1.5' from monument(S'thly).

TO REACH: From intersection located at the
Southwest corner of the Umpqua store parking lot
proceed E'stly along Co Rd. #9 1.5 mi. to mon. on right
VICINITY: Station is approx. 1.5 mi. ENE

of the Umpqua store.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.