

12/82


OFFICE OF THE

u-007
U-7 RESET

25S 7W 22

DOUGLAS COUNTY SURVEYOR

NAD	638949.87	4118838.71
83	43°22'49"	123°31' 9"

T 25 S, R 7W, Sec. 22Station: U-7 1972 RESET 1976Set By (Agency): DCSODate: 1976U-007NGVD29VERTICAL CONTROLElevation: 343.965 NGS(USC&GS) Line # _____ USGS Line # _____


Order

Of Precision 2nd Agency: DCSO Proj. #: 2006 Date: 1976HORIZONTAL CONTROLNAD 27Oregon State Plane Coordinates: Y(Northing) 638,984.48 X(Easting) 1,197,879.81
(South Zone)

Order

Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1976Approximate Geographic Position: Latitude= 43° 22' 49" Longitude= 123° 31' 04"DESCRIPTION: A STANDARD DOUGLAS COUNTYSURVEYORS OFFICE BRONZE DISK SET IN ADRILL HOLE IN A SANDSTONE BOULDER, LEVELWITH THE ROADWAY. 23 FT. FROM THE CENTER-LINE OF CO. RD. #33, 11 FT. N.E. OF THES'THLY R/W FENCE MARKED "U-7 1972 RESET1976".VICINITY: FROM THE INTERSECTION OF FORT MCKAY RD.(Co. Rd. #9) AND TYEE RD. (Co. Rd. #33) PROCEED NW'LY ALONG TYEE RD. 3.6 MI. TO MON. ON LEFT.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.