

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: N. SWIFT T 26 S, R 3 W, Sec 1

Set By (Agency): FED. HWY. ADMIN.

Date Set: \_\_\_\_\_

Recovered By RWS, SJF


Date Recovered 11/21/84

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



n-028  
N. SWIFT 26S 3W 1

NAD 617297.38 4254871.60  
83 43°19'59" 123° 0'19"

VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL NAD 27

South Zone State Plane Coordinates: Y(Northing) 617,333.30 X(Easting) 1,333,911.15

Precision: 1/15,000 Agency: DCSO Proj. # 6010-4 CS#60/7 Date: 1978

Approximate Geographic Position: Latitude 43°20'00" Longitude 123°00'14"


DESCRIPTION and TO REACH

A Fed. Hwy. Admin. disk stamped "N. SWIFT 1978" set flush in top of a concrete guardrail.

TO REACH:

From the intersection of Diamond Lake Highway (State Hwy. #138) and Swiftwater Rd. (USFS Rd. #26-3-1.1) in T26S, R3W, Sec.1, proceed southerly approx. 100 ft. to the north end of Swiftwater bridge. Monument lies to left in north end of easterly concrete guardrail. Monument is approx. 3 ft. above bridge deck.

SKETCH



Reference Marks:

A Fed. Hwy. Admin. disk stamped "S. SWIFT 1978" bears S 21°50'04" W, 373.78 ft. (grid).

~~A Bureau of Public Works disk stamped "HATCH 1978" bears N 89°08'00" E, 616.13 ft. (grid). DESTROYED 12/03 PER DCSO~~

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.