



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



Station: STENBECK
Date Set: 10-86
Set By (Agency): BENTZ SURVEY
DCSO Designation: S-156
Date Recovered: 11-86
Recovered By: SJF RWS
Date Recovered: _____
Recovered By: _____
Date Recovered: _____
Recovered By: _____

T26W R6W Sec. 28



VERTICAL CONTROL


NGVD 29 Elevation: _____ FEET NAVD 88 Elevation: _____ METERS
NGS Line # _____ USGS LINE # _____ OSHD Line # _____ FILE # _____
Precision: _____ Agency: _____ Proj: _____ Date: _____

HORIZONTAL CONTROL

O.C.S. 27 Y(Northing): 601,631.31 O.C.S. 83 Y(Northing): 601596.27
(South Zone) X(Easting): 1,225,545.05 (South Zone) X(Easting): 4,146,503.78
Precision: 1/5,000 Agency: DCSO Proj: 6001 Date: 11-86
Approx. O.C.S. 27 Geographic Position: Latitude: 43°16'50" Longitude: 123°24'32"
Approx. O.C.S. 83 Geographic Position: Latitude: 43°16'50" Longitude: 123°24'37"

Description: A 2 inch I.D. X 36 inch long galvanized iron pipe with a 5/8 inch iron rod, with a plastic cap marked BENTZ SURVEYING INC. in center, set approx. 6 inches below ground.

To reach: From the intersection of Del Rio Rd. (Co. Rd. #31C) and Garden Valley Rd. (Co. Rd. #31A) in T26S R6W Sec28 proceed southerly along Garden Valley Rd. approx. 1,100 feet to monument on left at east edge of road right-of-way in fence line.



Note: For further information contact the Douglas County Surveyors Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4272. Douglas County Residents outside Roseburg calling area, dial toll free 1-800-477-0991.