


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

u-129
UW-8

26S 7W 13

NAD 612658.04 4127767.74
83 43°18'32" 123°28'55"



T 26 S, R 7W, Sec. 13

Station: UW-8

Set By (Agency): DCSO

Date: 1974

VERTICAL CONTROL

NGVD 29

Elevation: 543.183 NGS(USC&GS) Line # _____ USGS Line # _____

Order

Of Precision 2nd Agency: DCSO Proj. #: 2007 Date: 1991

HORIZONTAL CONTROL

OCS 21

Oregon State Plane Coordinates: Y(Northing) 612,693.08 X(Easting) 1,206,808.72
(South Zone)

Order

Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1974


Approximate Geographic Position: Latitude= _____ Longitude= _____

DESCRIPTION: Station is a D.C. brass cap
set in concrete in a buried 6"x36" bell tile
20' W. of edge of pavement, and 50' S.W. of
and on opposite side of road from p. pole
#3-14. Cap is marked UW-8. From Melrose
store proceed Northerly on County Rd. #13
for 5.85 mi. to mon. Survey marker sign
bears S 70°W, 2.5 ft.

VICINITY: Umpqua-Melrose Rd. (Co. Rd. #13)

5+ mi. North of Melrose.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.